

December 3, 2025

POLK COUNTY, A POLITICAL SUBDIVISION OF THE STATE OF FLORIDA

ADDENDUM #2

BID # 25-712, Loyce E. Harpe Park Athletic Fencing Replacement

This addendum is issued to clarify, add to, revise and/or delete items of the Bid Document for this work. This Addendum is a part of the Bid Document and acknowledgment of its receipt shall be noted on the Addendum.

Contained within this addendum: questions and answers

Brad Howard

Sr. Procurement Analyst
Procurement Division

This Addendum sheet should be signed and submitted with your Bid submittal. This is the only acknowledgment required.

Signature: _____

Printed Name: _____

Title: _____

Company: _____

Bid # 25-712, Loyce E. Harpe Park Athletic Fencing Replacement Addendum # 2

- Q1: There is 1 3/4" diamond mesh located at the backstop of field 9. Is this to be replaced with standard 2" 6-gauge mesh or replaced with 1 3/4"?
- A2: The backstop will be 2" 6-gauge and the backstop overhang will be replaced with 1 3/4 9-gauge.
- Q2: In the scope of work for field 9, it calls for 4 ft high gates. The current gates at field 9 are 6ft high to match the fence. I assume we are replacing with 6ft high?
- A2: We want to go back with the existing size which are 6' H x 4' W.
- Q3: Are there requirements for the diameter, depth, and amount of concrete required for line post, terminal post, and backstop post?
- A4: This is a remove and replace. They should be rounded out with the line post 18" deep (1 bag concrete) and the backstop 3' deep (2 bags concrete).
- Q4: Is the 4 ft high galvanized fence located at the south entrance of the north quad included in the scope of work?
- A4: Yes.