

March 16, 2026

**POLK COUNTY, A POLITICAL SUBDIVISION OF
THE STATE OF FLORIDA
ADDENDUM #3
CQ #26-127 SM**

Parking Lot Improvements to Sheriff's Fleet Eaton Park

This addendum is issued to clarify, add to, revise and/or delete items of the Quote Document for this work. This Addendum is a part of the Quote Document and acknowledgment of its receipt shall be noted on the Addendum.

Contained within this addendum: Revisions to Scope of Work and Questions and Answers

Jason Flucker-Williams

Jason Flucker-Williams
Procurement Analyst
Procurement Division

This Addendum sheet should be signed and submitted with your quote submittal. This is the only acknowledgment required.

Signature: _____

Printed Name: _____

Title: _____

Company: _____

CQ 26-127 SM – Parking Lot Improvements to Sheriff's Fleet Eaton Park

Addendum #3

Revisions to Scope of Work

Area B:

1. Remove and sawcut existing concrete and replace it with concrete with two (2) areas 9' x 20' x 8" and 20' x 27' x 8".
2. Additional dowel bars at 18" O.C. with # 5 bars on all replaced concrete.
3. Dirt and concrete will be disposed of offsite at the expense of the contractor.

Area C:

1. Deduct 150' x 24' for mill and overlay.
2. Mill and overlay outside the perimeter of the Conex areas.
3. Removed millings will stay in the Sheriff's compound.
4. Behind fleet shop, the striping will be changed from straight lines to parallel lines.

Questions and Answers

Question 1: Instead of 3" of base can we go to 6" of base? Worried about future sagging/cracking of parking lot.

Answer 1: Yes, change to 6" of base and meet the minimum 95% of density for compaction

Question 2: Will the concrete on the south end need to be replaced?

Answer 2: Only the section shown in Area B of the specifications and the additions provided above for Revisions to Scope of Work that were discussed at the pre-quote meeting and site visit.

Question 3: Will the county take care of Geotechnical testing and sampling, or will the contractor need to do this?

Answer 3: The contractor is responsible for geotechnical testing and sampling. The contractor shall provide a copy of the compression test to the Facilities project manager.