

May 22, 2026

**POLK COUNTY, A POLITICAL SUBDIVISION OF
THE STATE OF FLORIDA
ADDENDUM #1
Bid #26-259**

Polk County Central Jail Cell Door Replacement

This addendum is issued to clarify, add to, revise and/or delete items of the Quote Document for this work. This Addendum is a part of the Quote Document and acknowledgment of its receipt shall be noted on the Addendum.

Contained within this addendum: Questions and Answers

Jason Flucker-Williams

Jason Flucker-Williams
Procurement Analyst
Procurement Division

This Addendum sheet should be signed and submitted with your quote submittal. This is the only acknowledgment required.

Signature: _____

Printed Name: _____

Title: _____

Company: _____

Bid 26-259 – Polk County Central Jail Cell Door Replacement

Addendum #1

Questions and Answers

Question 1: Please confirm that the facility needs the 500 model (side mount model). This is for cell doors that have the food port cut out on the side of the cell door. Based on the pictures of the cell doors in the spec sheets, it looks like the food port cut out is on the center of the cell door. That would require an MPACS 200 BOP model.

Answer 1: The intent and the design is to provide food ports that ensure staff protection. A MPACS 200 BOP Model would be required.

Question 2: According to DEC Scope of work the Security Electronic Wiring is included, but during our Bid meeting it was specified that all wiring was going to be reused. Can you please confirm?

Answer 2: The existing wiring is being reused. Reference the Typical Door Control Schematic Riser Diagram.

Question 3: Please clarify how to proceed at the construction access points, will DEC have to install temporary gates? Or whether the construction access points will require cutting and later mending of existing materials?

Answer 3: The Contractor is to remove the necessary section of the existing fence at each construction access point, set it aside, and reinstall it once the work in that area is complete.

Question 4: The list of Alternates shown on the drawings indicates all three (3) alternates include work in Building 2. However, the list of Alternates shown in the specifications indicates that each alternate corresponds to work in different buildings. Please clarify which building(s) each alternate applies to and confirm the correct location of work for each alternate.

Answer 4: Alternates IV, V and VI are all in Building 2 as shown on A1.1.

Question 5: Please confirm that existing frames are to remain and are not part of the scope of work.

Answer 5: The existing frames are to be left and are not part of the scope. All components such as rails, overhead enclosures, heads, slider doors etc. shall be demolished to accept the new units.

Bid 26-259 – Polk County Central Jail Cell Door Replacement

Addendum #1

Question 6: The DEC is to provide security electronic wiring – during the walk through we were informed that wire and wiring would remain. Is the DEC pulling new wire from the release cabinet to the field wire? (see page 18 out of 43 in specifications, 1.06, letter A #4)

Answer 6: The existing wiring is being reused. Refer to the Typical Door Control Schematic Riser diagram.

Question 7: Page 19 out of 43, number 5, letter G – is this applicable if damage is done to the existing opening?

Answer 7: Yes, this applies if damage is done, otherwise not applicable.

Question 8: Page 18 out of 43 states that the DEC is responsible for the relay system, intercommunication system, cell monitoring, and all cabling. Please clarify if a new detention controls system will be included in the DEC proposal or not.

Answer 8: A new detention control system will not be included. All items in 1119002; 1.07; A; 1-6 are existing and are to remain, as they are in current condition. Controls replacement will be performed by owner at a later date.

Question 9: According to page 41 out of 126, 7.8 tax is to be included, is this correct?

Answer 9: Yes, that's correct.

Question 10: Temporary fencing is to be provided by contractor, according to page 74 out of 126. Does this fencing include inside the secure fencing where the Connex will be located?

Answer 10: Temporary fencing outside the secure perimeter fence around the storage boxes is not required by the Owner. If the Contractor needs temporary fencing, for example, to secure an area for materials, then the Contractor is responsible for providing it. The intent is for the Contractor to provide secure storage as needed.

The fencing currently installed on site will be removed as necessary to allow construction access and will be replaced in the same condition once work in each area is completed. Access to the site will not be permitted for anyone other than Contractor personnel performing the work.