

July 15, 2026

**POLK COUNTY, A POLITICAL SUBDIVISION OF THE STATE
OF FLORIDA
ADDENDUM # 3
BID # 26-305, Road Construction - Minor**

This addendum is issued to clarify, add to, revise and/or delete items of the Bid Document for this work. This Addendum is a part of the Bid Document and acknowledgment of its receipt shall be noted on the Addendum.

Contained within this addendum: questions and answers received, and revisions.

Respectfully,
Divina Arroyo
Divina Arroyo
Procurement Analyst
Procurement Division

This Addendum sheet should be signed and submitted with your bid submittal. This is the only acknowledgment required.

Signature _____

Printed Name: _____

Title: _____

Company: _____

Bid # 26-305, Road Construction - Minor

Addendum # 3

Q1: Per the specifications, the contractor will get to price the following 4 LS items which are specific to each request; Clearing & Grubbing, MOT, Mobilizations, and Dewatering. Can you please confirm this?

A1: Yes.

Q2: Will unsuitable material be treated as an unknown and be paid through a change order?

A2: Yes, unless the unsuitable material is known ahead of time. In this case a price for the removal will be requested in the bid request.

Q3: Is FDOT approved pits required for the base material being supplied on this job?

A3: Yes.

Q4: Is FDOT approved mix designs for concrete and asphalt required on this project?

A4: Yes.

Q5: Does BABA or Buy America apply to this project?

A5: No.

Q6: What height Gravity wall should be assumed for pay item 32?

A6: Five feet plus one foot toe depth.

Q7: What Scheme Gravity wall is required for pay item 32?

A7: Scheme 1.

Q8: Are any special finishes required for pay item 32?

A8: No.

Q9: Are any flumes required around the DBI's, or will this be priced on a job by job basis?

A9: If flumes are required on a project, it will be considered as out of scope work, and a price will be requested for the work.

Q10: What depth should the storm pipe be assumed at less than 10'?

A10: On average, storm pipes are normally installed with around three feet of cover. For this bid, price the storm pipe installations at trench depth of ten feet.

Q11: Please confirm that the only structures requiring bars / grates have them mentioned in the pay item.

A11: Per FDOT Index #430-022, grates are required on round concrete pipe MES that is 30" and larger and on elliptical concrete pipe MES that is 19"x30" and larger. Grates are

Bid # 26-305, Road Construction - Minor Addendum # 3

required on round CMP MES that is 30" and larger, and on CMP arch MES that is 35"x24" and larger. The cost for all grate bars and fasteners is to be included in the unit price of the MES.

Q12: Please confirm that any cofferdam or bypassing of stormwater flow is to be included in the Mobilization cost for each individual work order?

A12: The cost of temporary cofferdams and stormwater bypass pumping is to be included in the dewatering price for each individual bid request.

Q13: Please clarify which type of trench drain is required for pay item 118.

A13: Type II with removable grate.

Q14: Please provide a detail for pay item 234, FDOT does not have a detail for this. Please confirm if native soil is required for backfill or if another material must be used.

A14: There is no bid item #234. There are only bid items #1 through #162.

Q15: Please confirm the depth required for pay item 231.

A15: There is no bid item #231. There are only bid items #1 through #162.

Q16: Can more parameters be provided for pay items 247 and 248 so the contractor knows how many weep holes are required?

A16: There are no bid items #247 or #248. There are only bid items #1 through #162.

Revision to Scope of Work (pg. 36) item 3 Projects Planned

Delete in its entirety: Projects that are currently planned to be constructed using this Bid include the following:

- a. CR 54 @ Mayfair Blvd
- b. Cypress Pkwy @ Lake Marion Creek Rd
- c. Kathleen Rd @ Deeson Rd
- d. Old Bartow / Lake Wales Rd @ SR 60
- e. Cypress Gardens Rd @ Lake Ned Rd roundabout
- f. CR 54 @ Heritage Pass
- g. CR 630 @ CR 630A roundabout
- h. Galloway Rd @ 10th St W roundabout
- i. CR 54 @ Westside Blvd
- j. Buckeye Loop Rd @ Country Club Rd
- k. CR 547 @ 10th St

Bid # 26-305, Road Construction - Minor Addendum # 3

Replace with the following: Projects that are currently planned to be constructed using this Bid include the following:

- Colbert Rd new sidewalk and minor road modifications
- Oak Dr @ Palmetto Dr minor road modifications
- Spirit Lake Rd @ US 17
- Mt Olive Rd @ SR 33
- Spirit Lake Rd @ Thornhill Rd new sidewalk and ADA improvements